Bill of Quantities

Riverside Community Clinic, Block B (fictional practice project)

Synthetic document created for learning purposes only. Not a real contract.

Rates are in currency units, excluding taxes. Quantities are estimated and subject to re-measurement.

Item	Description	Unit	Qty	Rate	Amount
1.1	Excavation for foundations in all types of soil, including disposal	m3	620	18	11,160
1.2	Backfilling in layers with compaction to 95% MDD	m3	310	9	2,790
2.1	PCC grade C15 below footings, 100 mm thick	m3	42	95	3,990
2.2	RCC grade C25 in isolated footings, including formwork	m3	185	140	25,900
2.3	RCC grade C30 in columns, including formwork	m3	96	150	14,400
2.4	RCC grade C30 in beams and slabs, including formwork	m3	410	145	59,450
3.1	Reinforcement steel Fe415 bars, cut, bent and placed	tonne	98	780	76,440
4.1	230 mm solid concrete block masonry in CM 1:6	m2	1,650	22	36,300
4.2	115 mm solid concrete block partitions in CM 1:4	m2	940	14	13,160
5.1	APP-modified bituminous roof membrane, 3 mm thick, with flood test	m2	780	12	9,360
6.1	600 x 600 mm anti-skid vitrified floor tiles on 20 mm CM bed	m2	1,320	28	36,960